



2020 Sewer Rehab project



The City of Brandon has contracted with Suncoast Infrastructure to install cured-in-place pipe liner in the areas indicated on the map as provided on the back of this info sheet. The cured-in-place pipe liner restores structural integrity to cracked and deteriorated underground pipes. Once installed into the host pipe, CIPP will inhibit ground water infiltration while reducing the volume flowing through the system and to the treatment facility. The high-quality resin and superior dry tube used to manufacture Suncoast® Liner provides exceptional strength and resistance to corrosion from harsh sewer gases. Suncoast® Liner is carefully manufactured to meet or exceed ASTM F-1216, the industry standard for cured-in-place piping.

Suncoast has installed the CIPP liner in both small and large diameter sewer lines and storm drains across the south. The projects include installations in small towns, large cities, airports, military bases, private systems, and industrial plants. The sewer lines located in the Crossgates area are approximately 50 years old. The concrete pipe has lost much of its original structural integrity. The CIPP liner will restore the pipe to a better than new condition.

CIPP LINER INSTALLATION



EXISTING PIPE – Stonegate Dr.





DRAWING TITLE		CITY OF BRANDON		REV	DATE	DESCRIPTION	DATE	BY
STONEGATE SEWER		CROSSGATES YEAR 1						
PROJECT TITLE		SEWER REHAB						
SHEET NO.		1						
DATE		11-28-2019						
POL. NO.		18-144						


Client Consultants, Inc.
 CONSULTANTS AND ENGINEERS
 10000 W. BAYVIEW BLVD., SUITE 100
 DALLAS, TEXAS 75243
 TEL: 972.382.1111
 FAX: 972.382.1112
 WWW.CCINC.COM